KILBUSH LANE

Exist 375ø S.W. Sewer.

New FMH. CL-6.34 Inlet-5.475 Invert-5141.

Exist. 100mmø Pvc watermain.

Recently constructed 375ø S.W. sewer.

Exist SMH

Exist SMH CL-6.34 New Inlet-5.60 Inv.-4.70

New connection to EXist SMH.

Exist. FMH.

Exist 300ø Foul Sewer.

DFH.

6.27

N.L.S.

SV.

New 100mmø pvc watermain.

Exist SV.

Exist FMH CL-6.38 IL-5.03

New 3 BED. GFL-6.70

GFL-6.70

GFL-6.70

Exist. 3BED S/DETACHED HOUSES.

Exist. Bungalow.

6.85

NEW 3BED COMBINATION HOUSES.

New 3 BED. GFL-7.05 8A 7A 6A 5A

GFL-7.05 8 7

GFL-7.05 6 5

Exist. 4BED S/DETACHED HOUSES

New 100mmøpvc watermain.

No Sign Marker

Hyd

N.L.S.

RG

SV (Missing)

Rad 6m

Exist. 225ø Foul Sewer @ 1:100

Exist. 100ø Watermain.

NEW SV.

RG (Buried)

6.0m

P.N.L.S.

SMH-4

New 225ø @ 1:180

SMH-3

Exist.225ø @ 1:98

SMH-2

SMH-1

FMH-1

Exist. 225ø @ 1:100

FMH SO26548201

7.33

9-10-11

OPEN SPACE.

P.N.L.S.

GFL-7.975

PARKING.

6.0m

1.5m

12-13-14

FMH-2 SMH-5

63mm PE GAS LINE

225ø @ 1:100

8.23

7.79

OPEN SPACE.

FMH-2

15-16

6m

GFL-8.150

17-18 19-20

150ø @ 1:80

225ø @ 1:100

8.17

PARKING.

18

21-22

C 9a-16a

KILBUSH LANE.

13

CAR PARK.

8.65

27

5.5m

9.15

8.86

12

8

7

1

3BED DETACHED TOWNHOUSE.

FL-9.40

9.28

24

Exist 150mmø Foul sewer.

3

BARRACK LANE

PUB.

Exist FMH CL-8.97 IL-7.20

Storey high mer Ballroom.

N

W E

S

| FOUL SEWER / SURFACE WATER SEWER | | | | | | | |
|---|---|---|---|---|---|---|---|
| MANHOLE No. | COVER LEVEL | INVERT LEVEL | PIPE DIAMETER (MM) | MANHOLE NO. | COVER LEVEL | INVERT LEVEL | PIPE DIAMETER (MM) |
| S026548201 | 7.25 | 5.88 / 5.58 | | S1 | - | | |
| | | | 225 | | | | 225 |
| F1 | 8.06 | 6.68 | | S2 | 7.42 | 6.02 | |
| | | | 225 | | | | 225 |
| F3 | 7.96 | | | S3 | 8.22 | 6.27 | |
| | | | 225 | | | | 225 |
| F4 | 8.44 | | | S4 | 7.40 | | |
| | | | | | | | 225 |
| | | | | S5 | 7.95 | | |

## REVISIONS

THIS DRAWING DOES NOT CONSTITUTE A RECOMMENDATION TO HAVE ESTATES TAKEN IN CHARGE / / INTO MAINTENANCE. FOR INFORMATION ON SAME SEE RELEVANT CORRESPONDENCE. THIS MAP REFERS TO TAKING INTO MAINTENANCE/CHARGE ONLY THOSE ROADS AND SERVICES AS INDICATED IN COLOUR.

EXCLUSIONS: COMMON AREAS IN THE DEVELOPMENT WHICH ARE SHOWN ON THE 'DEED OF CONVEYANCE' DOCUMENT ARE UNDER THE CONTROL OF THE MANAGEMENT COMPANY

SENIOR ENGINEER: Brendan Colgan — SURVEYED BY: AP/DG/CC

| | | | |
|---|---|---|---|
| DATE: | Nov 2014 | DRAWN BY: AP | NOTE : |
| CHECKED BY: | A.Popovic | BC No. 1384 | NOT TO SCALE |
| APPROVED BY: | C.Gallagher | SCALE: 1:250 | LENGTH OF ROADS ARE AS ON ATTACHED ROAD SCHEDULE. |
| CAD FILE REF: Cois Tra, Rush | | OS Ref. No. 2791-14 | |

Fingal

Comhairle Contae Fhine Gall
Fingal County Council

Inspectorate Division

# TAKING INTO CHARGE

## Cois Tra, Rush

ED - Rush TL -Rush

| | |
|---|---|
| Foul Sewer | Foul Sewer |
| Surface Water | Surface Water |
| Water Mains | Water Mains |
| Other | Hyd fire hydrant; DHyd duct fire hydrant; SV sluice valve; RG road gully |